BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42440

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work:Community property maintenance including parks in ward no 11 (Kuvempunagara)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MURTHY K G (ARM CONSTRUCTIONS)	
				In Figures	In Words
1	9.8	Filling the Foundation trenches using approved sand as per Drawing and technical Specification in 250mm layers wherever necessary watering and ramming including cost of all materials, labours, HMT etc complete as per specifications and directions of engineer in charge of the work	Cum	3053.83	Rupees Three Thousand Fifty Three and Eighty Three Paise Only
2	124	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	1058.14	Rupees One Thousand Fifty Eight and Fourteen Paise Only
3	111	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	No	409.99	Rupees Four Hundred Nine and Ninety Nine Paise Only
4	33.2	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	37.18	Rupees Thirty Seven and Eighteen Paise Only
5	33.2	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	85.41	Rupees Eighty Five and Forty One Paise Only
6	72	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) etc complete as per specifications and directions of engineer in charge of the work	M	863.19	Rupees Eight Hundred Sixty Three and Nineteen Paise Only
7	195	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	M	409.99	Rupees Four Hundred Nine and Ninety Nine Paise Only

Signature of the contractor

10/09

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MURTHY K G (ARM CONSTRUCTIONS)	
				In Figures	In Words
8	97.5	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	Sqm	718.49	Rupees Seven Hundred Eighteen and Forty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92